









1 K Plastic primer

Art.no. 412081

APPLICATION DATA

Mixing ratio	:		Product is ready to use.
Equipment	:		<u>Nozzle diameter (mm)</u> <u>Spraying pressure (bar)</u> Gravity feed 1.1 – 1.2 2.0 – 2.5
Spray coats Film thickness	:		1 full spray-coat , maximum 2 full spray coats. 5 -7 μm
Flash-off	:		No flash-off time.
Drying	:		Apply finish after 20 – 30 minutes, maximum 2 hours for finishing.
Storage Life	:		Under normal storage conditions 2 years in unopened tins.

Note :For Plastic substrates as: (Always test before using this product)

PP Polypropylene
ABS Acrylonitrile Butadiene Styrene
PUR Polyurethane
PC Polycarbonate
PA Polyamide (nylon)
EPDM Ethylene Propylene Diene Mixed Polymeer

Do not use on Polythylen or Polystyrene.

For more info please contact info@carolux.nl

The technical data in these publications are based on our present knowledge and give you an idea of the various applications without obligations. [okt-16]